



Technical Specifications:-

- Open – circuit, suck – down wind tunnel
- Test section size: 1m w x 0.80m h x 1.5m l
- Test section flow speed: 0 – 25 m/s
- With 4 axial ducted fans (6hp each)
- With 4 variable frequency drive
- Inclusive of the support frames and I – beam leveler
- Clear polycarbonate walls and floor of the test section
- With smoke injector for flow visualization

Note: Specifications are subject to change, Photos shown above are Indicative, Actual Product can Vary.



Export Sales: +91-9829132777
India Sales: +91-9588842361



IT-2013, Ramchandrapura Industrial Area,
Sitapura Extension, Jaipur-302022, India.



info@tesca.in
www.tescaglobal.com